NOTE:
THE ZEROS IN PARENTHESES (0, 0.0 & 0.000) INDICATE THE DIMENSIONAL PRECISION FOR THAT COLUMN

NOTE:
FOR PIPE CULVERT PLACEMENT SEE STANDARD DRAWINGS C-13.10 AND C-13.15

NOTE:
PIPE OPTIONS SELECTED ARE THOSE REQUIRED TO MEET MINIMUM SERVICE LIFE.
ALLOWABLE PIPE OPTIONS ARE INDICATED WITH THE LETTER 'X' IN THE SPACE. BLANK SPACES ARE NOT ALLOWABLE ALTERNATES.

CSP - CORRUGATED STEEL PIPE
CAP - CORRUGATED ALUMINUM PIPE
RCP - REINFORCED CONCRETE PIPE
NRCP - NON-REINFORCED CONCRETE PIPE
NRCIPCP - NON-REINFORCED CAST-IN-PLACE CONCRETE PIPE
CHDPEP - CORRUGATED HIGH-DENSITY POLYETHYLENE PIPE
CPPP - CORRUGATED POLYPROPYLENE PIPE

Station	Plan Reference Number	Controlling Fill Height Range	Size, Corrugated (In.)	Size, Smooth (In.)	Length (0) (Ft.)	Skew (0) (Degree)	Corrugation	Wall Thickness (0.000)	Zinc (Coating)	Bituminous Coated Zinc (Coating)	Aluminum (Coating)	Bituminous Coated Aluminum (Coating)	Corrugation	Wall Thickness (0.000)	Uncoated (CAP)	Bituminous Coated (CAP)	Class - Non-Trench (CAP)	Class - Trench (CAP)	Class (RCP)	Minimum Wall Thickness (0) (RCP)	AASHTO M-294 Type S (NRCP)	AASHTO M-330 Type S (NRCIPCP)	C-13.20 & C-13.25 (CHDPEP)	Detail (CHDPEP)	Size, (In) Manhole (CPPP)	Standard or Detail (End Section)	S-Single / D-Double (Ea)	Location (Each)	H (0.0) (Catch Basin, Manhole, Headwall & Junction Structure)	L Wing (0.0) (Ft.)	L 18" Slotted Drain (0) (Ft.)	L 24" Slotted Drain (0) (Ft.)	Type (Grate)	Elevation (0.00) (Ft.)	Depth (Ft.)	L (0.0) (Ft.)	Inlet Depression C-15.70 (In.)	Pipe Excavation (0) (Cubic Yard)	Pipe Backfill (0) C-13.15 (Cubic Yard)	Drainage Excavation (0) (Cubic Yard)	Berm/Dike Embankment (0) (Cubic Yard)	REMARKS
Kino Pkwy Sta 15+56.16, 70.33' Rt.	400	2		18	40											II	II								C-15.10		RT	4.30				C-15.50	2513.95			40	15			CB-400 to Pipe Collar
Kino Pkwy Sta 15+53.22, 31.97' Rt.																																									Connect to Exst Pipe
Kino Pkwy Sta 16+00.30, 48.96' Lt.	402	3		18	12											II	II			X					C-15.10		LT	4.14				C-15.50	2514.56			14	5			CB-402 to Pipe Collar
Kino Pkwy Sta 15+99.21, 63.11' Lt.																																									Connect to Exst Pipe
Kino Pkwy Sta 16+95.36, 48.22' Lt.	404	3		18	12											II	II			X					C-15.10		LT	4.41				C-15.50	2514.96			13	4			CB-404 to MH-403
Kino Pkwy Sta 16+90.00, 37.46' Lt.																																									
Kino Pkwy Sta 18+90.00, 50.58' Rt.	414	5		36	103											IV	IV								C-15.10	D	RT	13.87				C-15.50	2516.47			444	64			CB-414 to CB-416
Kino Pkwy Sta 18+90.00, 50.58' Lt.	416	5		36	78											IV	IV								C-15.10	D	LT	14.25				C-15.50	2516.47			302	48			CB-416 to End Section
Kino Pkwy Sta 19+16.72, 124.54' Lt.																						1																			
Kino Pkwy Sta 18+90.00, 126.09' Rt.	418	4		36	73											III	III			X					SD-6.30		RT									207	46			HW to CB-414
Kino Pkwy Sta 18+90.00, 50.58' Rt.																																									
Kino Pkwy Sta 25+05.00, 50.80' Lt.	420	3		24	135											II	II			X					C-15.92		LT	4.32				C-15.92	2532.18	1	10	221	63			CB-420 to End Section
Kino Pkwy Sta 25+05.00, 188.21' Lt.																						1																			RCP End per Detail DX
Kino Pkwy Sta 25+55.00, 9.90' Rt.	426	2		24	149											II	II			X					C-15.92		RT	5.40				C-15.50	2534.33	1	10	15	69			CB-426 to End Section
Kino Pkwy Sta 25+32.36, 155.79' Rt.																						1																			RCP End per Detail DX
																						3	0	0						0	0					1256	314	0	0	

NO.	DESCRIPTION OF REVISIONS	BY	DATE
0	RFC RELEASE	TM	08/19/25

FILL HEIGHT RANGE TABLE (Ft.)

RANGE NO.		1	2	3	4	5	6	7	8	9	10	11	12
FILL	>	1	3	5	8	11	15	20	25	30	40	55	70
HEIGHT (Ft.)	≤	3	5	8	11	15	20	25	30	40	55	70	90

SHOULD FIELD CONDITIONS VARY FROM THE RANGE INDICATED, CONTACT DESIGN FOR RE-EVALUATION OF PIPE DESIGN REQUIREMENTS.

PIPE CORRUGATION

A	2⅔x½	D	6x2
B	3x1	E	3x1 or 9x2½
C	9x2½		

Registered Professional Engineer (Civil) CERTIFICATE NO. 65939 TIMOTHY MAHON Date Signed ARIZONA, U.S.A.

	NAME	DATE
DESIGN	J. FLINT	8/25
DRAWN	L. BREINING	8/25
CHECKED	T. MAHON	8/25

SUNDT AZTEC TYPSA

ARIZONA DEPARTMENT OF TRANSPORTATION
INFRASTRUCTURE DELIVERY AND OPERATIONS DIVISION
ROADWAY DESIGN SECTION

NEW PIPE SUMMARY SHEET

ROUTE I-10
MILEPOST
STRUCTURE NO.

F.H.W.A. Arizona Division

STATE	PROJECT NO.	FEDERAL ID NO.	SHEET NO.	TOTAL SHEETS	RECORD DRAWING
ARIZ.	010 PM 262	010-E(232)S			

LOCATION I-10 COUNTRY CLUB RD AND KINO PKWY TIS

DWG NO. G-04.30

TRACS NO. F0548 01C

ADOT

____ OF ____